



GRAIN STORAGE CENTRES 2002
REGIONAL NSW AND QLD

CLIENT:
AWB LIMITED

PROJECT VALUE:
\$45.0M

DURATION:
MAY 2002 -
SEPT 2003



This project is a Lump Sum Contract to Design and Construct nine Grain Receiveal Centres located in regional New South Wales and Queensland.

Kerman Contracting Limited (KLC) was responsible for the design, supply and construct all structural, mechanical and electrical components as well as earthworks, roadworks and drainage.

KCL's responsibilities included the design and construction of two 1,350 tonne Storage Bins, all structural and mechanical components for the 600 tph inloading system from receiveal pit to storage bins and bulkheads including the total electrical installation for each site.

KCL is also responsible for all site weigh-bridges, sampling stations, open bulkheads, ground conveyors and propriety stackers.



Kerman Contracting Limited ACN 008 987 988 REF: 025